

OBIECTIV: DJ162 KM 16+250
Beneficiar: JUDEȚUL BISTRITA-NASAUD

| NR. | DENUMIRE | U.M. | CANTITATE | P.U. | TOTAL |
|---------------------------------------|---|-------|-----------|------|-------|
| DJ162 KM 16+250 | | | | | |
| 1 COLOANE FORATE D=800MM | | | | | |
| 1.1 | Sapatura mecanica | 100mc | 3.72 | | - |
| 1.2 | Strat din balast | mc | 155.00 | | - |
| 1.3 | Forare coloane D=800mm | m | 462.00 | | - |
| 1.4 | Confectionare si montare armatura B500C - piloti | kg | 25.986.00 | | - |
| 1.5 | Turnare beton C30/37 - in pilot | mc | 233.31 | | - |
| 1.6 | Spargere beton cap pilot | mc | 21.21 | | - |
| 1.7 | Incarcari nedestructive pe coloane forate - control sonic | buc | 42.00 | | - |
| 2 RADIER SI ELEVATII | | | | | |
| 2.1 | Sapatura | 100mc | 1.55 | | - |
| 2.2 | Turnare beton C12/15 | mc | 8.24 | | - |
| 2.3 | Cofraje | mp | 318.00 | | - |
| 2.4 | Confectionare si montare armatura B500C | kg | 9,114.00 | | - |
| 2.5 | Montare barbacane DN110mm | m | 12.60 | | - |
| 2.6 | Turnare beton C30/37 | mc | 114.90 | | - |
| 2.7 | Rosturi din polistiren | mp | 10.92 | | - |
| 2.8 | Hidroizolatii cu bitum | mp | 176.40 | | - |
| 2.9 | Umplutura din balast | mc | 147.00 | | - |
| 3 REFACERE DRUM SI ACOSTAMENTE | | | | | |
| 3.1 | Pregatire platforma | 100mp | 2.77 | | - |
| 3.2 | Strat din balast | mc | 128.00 | | - |
| 3.3 | Strat din piatra sparta | mc | 18.56 | | - |
| 3.4 | Strat din BAD22,4 | to | 34.56 | | - |
| 3.5 | Strat din BA16 | mp | 240.00 | | - |
| 3.6 | Geogrila antifisura | mp | 240.00 | | - |

| | | | | |
|----------------------|------------------------|---|-------|---|
| 3.7 | Parapet metalic tip N2 | m | 60.00 | - |
| TOTAL (exclusiv TVA) | | | | - |
| TVA 19% | | | | - |
| TOTAL (inclusiv TVA) | | | | - |

DIRECTOR EXECUTIV
CIPRIAN CECLAN-OPREA

ŞEF SERVICIU
VICTOR POIENAR